

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>ML-47560</b>	6. SURFACE: <b>State</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>	
B. TYPE OF WELL: <b>OIL</b> <input type="checkbox"/> <b>GAS</b> <input checked="" type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: <b>Stewart Petroleum Corporation</b>				9. WELL NAME and NUMBER: <b>Cedar Camp 34-15</b>	
3. ADDRESS OF OPERATOR: <b>475 17th St., Ste. 1250</b> CITY <b>Denver</b> STATE <b>CO</b> ZIP <b>80202</b>			PHONE NUMBER: <b>(303) 799-1922</b>		
4. LOCATION OF WELL (FOOTAGES) <b>631101X    4368230Y</b> AT SURFACE: <b>1,222' FSL &amp; 2,358' FEL, SW1/4 SE1/4, Section 34, T15-1/2S, R22E, SLB&amp;M</b> AT PROPOSED PRODUCING ZONE: <b>39.45555    -109.47624</b>				11. QTRQTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>44.95 miles southeast of Ouray, Utah</b>				12. COUNTY: <b>Grand</b>	13. STATE: <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>1,222'</b>		16. NUMBER OF ACRES IN LEASE: <b>915.60</b>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>4,015'</b>		19. PROPOSED DEPTH: <b>10,900</b>		20. BOND DESCRIPTION: <b>Bond #N3145</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>7,434' GR</b>		22. APPROXIMATE DATE WORK WILL START: <b>12/1/2007</b>		23. ESTIMATED DURATION: <b>21 days drilling, 40 days comp.</b>	

**PROPOSED CASING AND CEMENTING PROGRAM**

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
20"	16"	Cond.	0.250"	60	
12-1/4"	9-5/8"	K-55	36#	1,000	see Drilling Plan
7-7/8"	5-1/2"	N-80	17#	9,900	see Drilling Plan
7-7/8"	5-1/2"	P-110	17#	10,900	see Drilling Plan

**ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |   |  |
|---|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER<br><input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN<br><input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |
|---|--|

NAME (PLEASE PRINT) <u>Don Hamilton</u>	TITLE <u>Agent for Stewart Petroleum Corporation</u>
SIGNATURE <u>Don Hamilton</u>	DATE <u>10/9/2007</u>

(This space for State use only)

API NUMBER ASSIGNED: 43019-31561

APPROVAL:

**RECEIVED**


**OCT 16 2007**

**DIV. OF OIL, GAS & MINING**

*T15 1/2S, R22E, S.L.B.&M.*

# STEWART PETROLEUM CORPORATION


Well location, STATE #34-15, located as shown in the SW 1/4 SE 1/4 of Section 34, T15 1/2S, R22E, S.L.B.&M. Grand County, Utah.



**T15S**  
**T15 1/2S**

## BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE SE CORNER OF SECTION 30, T15S, R22E, S.L.B.&M. TAKEN FROM THE CEDAR CAMP CANYON, QUADRANGLE, UTAH, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7454 FEET.



SCALE

## CERTIFICATE

THIS IS TO CERTIFY THAT THE SURVEY WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE



## BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(AUTONOMOUS NAD 83)  
LATITUDE = 39°27'19.54" (39.455428)  
LONGITUDE = 109°28'37.96" (109.477211)  
(AUTONOMOUS NAD 27)  
LATITUDE = 39°27'19.66" (39.455461)  
LONGITUDE = 109°28'35.51" (109.476531)

## LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

**UINTAH ENGINEERING & LAND SURVEYING**  
**85 SOUTH 200 EAST - VERNAL, UTAH 84078**  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 10-01-07	DATE DRAWN: 10-01-07
PARTY J.W. J.S. S.L.	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE STEWART PETROLEUM CORPORATION	

October 9, 2007

Mrs. Diana Mason  
State of Utah  
Division of Oil Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill - Stewart Petroleum Corporation  
**Cedar Camp #34-15** - 1,222' FSL & 2,358' FEL, SW/4 SE/4,  
Section 34, T15-1/2S, R22E, SLB&M, Grand County, Utah

Dear Mrs. Mason:

On behalf of Stewart Petroleum Corporation, Buys & Associates, Inc. respectfully submits the enclosed original and one copy of the Application for Permit to Drill (APD) for the above referenced SITLA surface and mineral vertical well. A request for exception to spacing (R649-3-3) is hereby requested based on topography since the well is located within 460' of the drilling unit boundary. Stewart Petroleum Corporation is the only owner and operator within 460' of the proposed well and all points along the intended well bore path. Included with the APD is the following supplemental information:

Exhibit "A" - Survey plats, layouts and photos of the proposed well site;

Exhibit "B" - Proposed location maps with access corridor;

Exhibit "C" - Drilling Plan;

Exhibit "D" - Surface Use Plan;

Exhibit "E" - Typical BOP and Choke Manifold diagram.

Please accept this letter as Stewart Petroleum Corporation's written request for confidential treatment of all information contained in and pertaining to this application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Daryl Stewart of Stewart Petroleum Corporation at 303-799-1922 if you have any questions or need additional information.

Sincerely,

*Don Hamilton*

Don Hamilton  
Agent for Stewart Petroleum Corporation

cc: Daryl Stewart, Stewart Petroleum Corporation  
Lavonne Garrison, SITLA  
Ed Bonner, SITLA

**RECEIVED**  
**OCT 16 2007**  
DIV. OF OIL, GAS & MINING

**CONFIDENTIAL**

# DRILLING PLAN

## Attachment for Permit to Drill

**Name of Operator:** Stewart Petroleum Corporation  
**Address:** 475 17th St., Ste. 1250  
Denver, CO 80202  
**Well Location:** Cedar Camp # 34-15  
Surface: 1,222' FSL & 2,358' FEL, SW/4 SE/4,  
Sec. 34, T15-½S, R22E, SLB&M  
Grand County, UT  
Elevation 7,434'

### 1. GEOLOGIC SURFACE FORMATION Green River

### 2 & 3. ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS AND ANTICIPATED WATER, OIL, GAS OR MINERALS

<u>Formation</u>	<u>Depth (MD)</u>	<u>Depth (TVD)</u>	<u>Depth (TVD subsea)</u>	<u>Oil/Gas Zones</u>
Wasatch	900		6446	oil or gas
Mesaverde	2970		4376	gas
Castlegate	4800		2546	gas
Mancos	5000		2346	gas
Dakota Silt	8800		(1254)	gas
Cedar Mtn	9000		(1454)	gas
Entrada	9800		(2254)	gas
Wingate	9300		(2654)	gas
TD	10900			

### 4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.  
subject to review on the basis of actual conditions encountered.

	<u>Depth</u>	<u>hole size</u>	<u>Csg O.D.</u>	<u>Grade</u>	<u>Weight/Ft</u>
Conductor	60'	20"	16"	Contractor	0.250" wall
Surface	1,000'	12 1/4"	9 5/8"	K-55	36# new
Production	0-9,900'	7 7/8"	5 1/2"	N-80	17# new
	9,900'-10900'	7 7/8"	5 1/2"	P-110	17# new

### 5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized.

Intermediate hole: To be drilled using a diverter stack with rotating head to divert flow from rig floor.

Production hole: Prior to drilling out the intermediate casing shoe, 5,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from surface to total depth. The blind rams will be tested once per day from surface to total depth if operations permit.

## DRILLING PLAN

### APPROVAL OF OPERATIONS

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 5,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set.. All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

1.	Annular BOP	1,500 psi
2.	Ram type BOP	5,000 psi
3.	Kill line valves	5,000 psi
4.	Choke line valves and choke manifold valves	5,000 psi
5.	Chokes	5,000 psi
6.	Casing, casinghead & weld	1,500 psi
7.	Upper kelly cock and safety valve	5,000 psi
8.	Dart valve	5,000 psi

#### 6. MUD SYSTEMS

- Drilling fluids: Well will be drilled with a low solids non-dispersed mud. In the event of severe lost circulation the mud be aerated.
- The mud system will be monitored manually/visually.

<u>Interval</u>	<u>Mud Weight (ppg)</u>	<u>Viscosity</u>	<u>Fluid Loss</u>	<u>Remarks</u>
0 – 60'	8.3 – 8.6	27-40	--	Native Spud Mud
60' – 1,000'	8.3 – 8.6	27-40	15 cc or less	Native/Gel/Lime
1,000' – TD	8.6 – 9.5	38-46	15 cc or less	Potassium Formate

#### 7. BLOOIE LINE

- An automatic igniter will not be installed on blooie line. The blooie will have a constant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 80' from the wellhead.

#### 8. AUXILIARY EQUIPMENT TO BE USED

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string
- c. Float Sub at bit—No
- d. Mud logger & Instrumentation--Yes

#### 9. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- DST's: none expected
- Logging: DIFL/SP/GR TD to surface
- SDL/CNL/CAL w/ DFIL from TD to 2,500'
- Sonic/GR/Cal from TD to surface
- Mudlogger from Wasatch to TD
- Coring: none planned

#### 10. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

- No abnormal pressures or hydrogen sulfide are anticipated based on drilling within the immediate area.
- In Flat Rock Field, approximately 4.5 miles to the northwest, the Del-Rio/Orion #29-7A produced a 36 hour shut in pressure of 3,100 psi and a calculated formation pore pressure of approximately 4,000 @ 11,700'.

## DRILLING PLAN

### APPROVAL OF OPERATIONS

#### 11. WATER SUPPLY

- Produced water from offset field operations will be utilized to drill this well.
- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Exhibit "B".
- If supplemental water is required it will be obtained from the following source: Water Permit # 49-123 (A8815), Priority Date: 05/09/1921 (DeLambert, Burt and Christine) through an approved temporary application t33231 filed was on 7-25-07 and later approved is on 8-7-07 valid until 8-7-08

#### 12. CEMENT SYSTEMS

**Conductor:** 0-60' Ready mix to surface

##### **Surface Casing:** 0-1000'

Lead: 200 sx HiFill w/ 0.125 lbm/sk Poly E-Flake

Tail: 145 sx Premium AG 300 (class G) w/ 2% CaCl & 0.125 lbm/sk Poly E-Flake

100% excess. Will top w/ cement down 1" pipe w/ 50 sx Premium top out cement

Cement Characteristics: Lead:

Yield: 3.12 cu ft/sk

Slurry weight: 11.6 ppg

Compressive strength: 500 psi (24 hrs @ 80 degrees F)

Tail:

Yield: 1.17 cu ft/sk

Slurry weight: 15.8 ppg

Compressive strength: 3000 psi (24 hrs @ 80 degrees F)

##### **Production Casing:** 0-10,900;

Lead 30 sx 50:50 pozmix w/ 5 lbm/sk silicalite

Primary: 1,200 sx 50:50 pozmix w/ 5 lbm/sk silicalite

Tail: 25 sx 50:50 pozmix w/ 5 lbm/sk silicalite

15% excess

Cement Characteristics:

Yield: 1.47 cu ft/sk

Slurry weight: (not foamed): 14.3 ppg

Slurry weight: (foamed): 11.0 ppg

Compressive strength: 1,125 psi (24 hrs @ 140 degrees F; 1,500 psi)

**Actual cement volumes will be based on caliper calculations**

#### 13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: December 1, 2007

Duration: 21 days

## **SURFACE USE PLAN**

### Attachment for Permit to Drill

<b>Name of Operator:</b>	Stewart Petroleum Corporation
<b>Address:</b>	475 17th St., Ste. 1250 Denver, CO 80202
<b>Well Location:</b>	Cedar Camp # 34-15 Surface: 1,222' FSL & 2,358' FEL, SW/4 SE/4, Sec. 34, T15-½S, R22E, SLB&M Grand County, UT Elevation 7,434'

The dirt contractor will be provided with an approved copy of this document prior to initiating construction. The well site and access road is located on SITLA surface and SITLA mineral.

### **1. Existing Roads**

- a. Proposed access road will utilize the native surfaced Grand County Road 194 (Seep Ridge to Hay Canyon road) to the native surfaced Grand County Road 206 (Winter Ridge Road) to the county line (Uintah / Grand). From that point access will continue along the native surfaced Grand County Road (5660 (Winter Ridge Road) to a point in adjacent Section 32, T15S, R22E, SLB&M (See Exhibit "B").
- b. A Uintah County road encroachment permit will be secured for upgrade of the existing approach located in Section 32, T15S, R22E, SLB&M.
- c. We do not plan to change, alter or improve upon any other existing state or county roads.
- d. All existing roads will be maintained and kept in good repair during all phases of operation.
- e. Vehicle operators will obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions.

### **2. Planned Access Roads**

- a. From the existing native surfaced Uintah County Road 5660 (Winter Ridge Road) a new access is proposed trending south approximately 0.8 miles. From that point 0.7 miles of existing two-track access is proposed for upgrade to the proposed well site. The access consists of 0.7 miles of two-track

upgrade and 0.8 miles of new disturbance that crosses no significant drainages.

- b. A road design plan is not anticipated at this time.
- c. The proposed access road will consist of a 24' travel surface within a 30' disturbed area across SITLA surface.
- d. SITLA approval to construct and utilize the proposed access road is requested with this application.
- e. Planned access does not cross federal or Ute Tribal lands.
- f. A maximum grade of 10% will be maintained throughout the project with no major cuts and fills anticipated.
- g. No turnouts are proposed since the access road is only 1.5 miles long and adequate site distance exists in all directions.
- h. Several low water crossings and no culverts are anticipated. Adequate drainage structures will be incorporated into the remainder of the road.
- i. No surfacing material will come from federal or State lands.
- j. No gates or cattle guards are anticipated at this time.
- k. Surface disturbance and vehicular travel will be limited to the approved location access road.
- l. The operator will be responsible for all maintenance of the access road including drainage structures.

### **3. Location of Existing Wells**

- a. See Exhibit "B". There are no proposed and no existing wells within a one mile radius of the proposed location.



#### **4. Location of Existing and/or Proposed Facilities**

- a. If the well is deemed productive a sundry notice reflecting the production site layout will be submitted for approval
- b. Rehabilitation of all pad areas not used for production facilities will be made in accordance with SITLA stipulations.
- c. A gas pipeline is associated with this application and is being applied for at this time. The proposed gas pipeline corridor will leave the northeast side of the well site and traverse 7,647' north along the proposed access road to the existing Cedar Camp pipeline.
- d. The new gas pipeline will be a 12" or less steel surface line within a 40' wide disturbed pipeline corridor. The use of the proposed well site and access roads will facilitate the staging of the pipeline construction. A new surface pipeline length of approximately 1.5 miles is associated with this well.
- e. Stewart Petroleum Corporation intends to surface lay the pipeline and connect the pipeline together utilizing conventional welding technology.

#### **5. Location and Type of Water Supply**

- a. The location and type of water supply has been addressed as #11 within Exhibit "D". (Drilling Plan).

#### **6. Source of Construction Materials**

- a. Any necessary construction materials needed will be obtained locally from a private source and hauled to the location on existing roads.

#### **7. Methods for handling waste disposal**

- a. A small reserve pit will be constructed with a minimum of one-half the total depth below the original ground surface on the lowest point within the pit. The pit will be lined with a synthetic liner. Three sides of the reserve pit will be fenced within 24 hours after completion of construction and the fourth side within 24 hours after drilling operations cease with four strands of barbed wire, or woven wire topped with barbed wire to a height of not less than four feet. The fence will be kept in good repair while the pit is drying.

- b. Following drilling, the liquid waste will be evaporated from the pit and the pit backfilled and returned to natural grade. No liquid hydrocarbons will be discharged to the reserve pit or location.
- c. In the event fluids are produced, any oil will be retained in tanks until sold and any water produced will be retained until its quality can be determined. The quality and quantity of the water will determine the method of disposal.
- d. Trash will be contained in a portable metal container and will be hauled from location periodically and disposed of at an approved disposal site. Chemical toilets will be placed on location and sewage will be disposed of at an appropriate disposal site.

## **8. Ancillary Facilities**

- a. We anticipate no need for ancillary facilities with the exception of trailers to be located on the drill site.

## **9. Well-site Layout**

- a. Available topsoil will be removed from the location and stockpiled. The location of the rig, reserve and blooie pits, and drilling support equipment will be located as shown on Exhibit "A", Figure 1 (Location Layout).
- b. A blooie pit will be located 100' from the drill hole. A line will be placed on the surface from the center hole to the blooie pit. The blooie pit will not be lined, but will be fenced on four sides to protect livestock/wildlife.
- c. Access to the well pad will be as shown on the location layout.
- d. Natural runoff will be diverted around the well pad as shown on the location layout.

## **10. Plans for Restoration of Surface**

- a. All surface areas not required for producing operations will be graded to as near original condition as possible and contoured to maintain possible erosion to a minimum.
- b. Available topsoil will be stockpiled and will be evenly distributed over the disturbed areas and the area will be reseeded as prescribed by the SITLA.
- c. Pits and any other area that would present a hazard to wildlife or livestock will

be fenced off when the rig is released and removed.

- d. Any oil accumulation on the pit will be removed or overhead flagged as dictated by then existing conditions.
- e. Rehabilitation will commence following completion of the well. Holes will be filled immediately upon release of the drilling rig from the location. If the well-site is to be abandoned, all disturbed areas will be re-contoured to the natural contour as is possible.

#### **11. Surface Ownership**

- a. Surface Ownership – State of Utah – under the management of the SITLA - State Office, 675 East 500 South, Suite 500, Salt Lake, City, Utah 84102-2818; 801-538-5100.
- b. Mineral Ownership – State of Utah – under the management of the SITLA - State Office, 675 East 500 South, Suite 500, Salt Lake, City, Utah 84102-2818; 801-538-5100.
- c. The operator shall contact the surface representative and the Division of Oil, Gas and Mining 48 hours prior to beginning construction activities.

#### **12. Other Information:**

- a. The primary surface use is wildlife habitat and grazing. The nearest dwelling is in over 5 miles east of the proposed location. The nearest live water is the intermittent Meadow Creek 0.51 miles south.
- b. If there is snow on the ground when construction begins, it will be removed before the soil is disturbed, and piled downhill from the topsoil stockpile location.
- c. The back-slope and fore-slope will be constructed no steeper than 3:1.
- d. All equipment and vehicles will be confined to the access road and well pad.
- e. A complete copy of the approved Application for Permit to Drill (APD) including conditions and stipulations and the surface use agreement shall be on the well-site during construction and drilling operations.
- f. There will be no deviation from the proposed drilling and/or workover program without prior approval from the Division of Oil, Gas & Mining.

**13. Company Representative**

Daryl Stewart  
Stewart Petroleum Corporation  
475 17th St., Ste. 1250  
Denver, CO 80202  
(303) 799-1922

**Company Agent**

Don Hamilton  
Buys & Associates, Inc  
2580 Creekview Road;  
Moab, Utah 84532  
435-718-2018

**14. Certification**

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed by Stewart Petroleum Corporation and its subcontractors in conformity with this plan and the terms and conditions under which it is approved.

10-9-2007  
Date

Don Hamilton  
Don Hamilton  
Agent for Stewart Petroleum Corporation

# STEWART PETROLEUM CORPORATION

## CEDAR CAMP #34-15

SECTION 34, T15 1/2S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 54.9 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 7.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 6.0 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTH; FOLLOW ROAD FLAGS IN A SOUTHERLY DIRECTION APPROXIMATELY 0.8 MILES TO AN EXISTING TWO-TRACK ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 100.4 MILES.


# STEWART PETROLEUM CORPORATION

FIGURE #1

## LOCATION LAYOUT FOR

CEDAR CAMP #34-15  
SECTION 34, T15 1/2S, R22E, S.L.B.&M.  
1222' FSL 2358' FEL

Approx.  
Toe of  
Fill Slope



SCALE: 1" = 50'  
DATE: 10-01-07  
Drawn By: S.L.

Approx.  
Top of  
Cut Slope.

Reserve Pit Backfill  
& Spoils Stockpile

### NOTE:

Flare Pit is to be located  
a min. of 100' from the  
Well Head.

FLARE PIT

C-13.2'  
El. 444.5'

El. 461.7'  
C-40.4'  
(btm. pit)

10' WIDE BENCH

RESERVE PITS  
(10' Deep)  
Total Pit Capacity  
W/2' of Freeboard  
= 14,580 Bbls. ±  
Total Pit Volume  
= 4,020 Cu. Yds.

Sta. 0+85

El. 466.2'  
C-44.9'  
(btm. pit)

### NOTES:

Elev. Ungraded Ground At Loc. Stake = 7434.3'  
FINISHED GRADE ELEV. AT LOC. STAKE = 7431.3'

PIPE TUBS

CATWALK

PIPE RACKS

C-3.0'  
El. 434.3'

RIG

DOG HOUSE

LIGHT PLANT

BOILER

COMPRESSOR

BOOSTER

PUMP HOUSE

MUD TANKS

TRASH

PROPANE STORAGE

TOILET

TRAILER


WATER TANK

Sta. 0+50

Sta. 0+00

Proposed Access  
Road

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017



EXISTING 2-TRACK

Round Corners  
as Needed

Sta. 3+75

F-18.8'  
El. 412.5'

F-21.2'  
El. 410.1'

F-34.4'  
El. 396.9'

F-0.1'  
El. 431.2'

C-7.9'  
El. 439.2'

C-10.9'  
El. 442.2'

C-9.6'  
El. 440.9'

C-1.1'  
El. 432.4'



# STEWART PETROLEUM CORPORATION

FIGURE #2

## TYPICAL CROSS SECTIONS FOR

CEDAR CAMP #34-15  
SECTION 34, T15 1/2S, R22E, S.L.B.&M.  
1222' FSL 2358' FEL

X-Section Scale  
1" = 20'  
1" = 50'  
DATE: 10-01-07  
Drawn By: S.L.



### APPROXIMATE YARDAGES

CUT  
(6") Topsoil Stripping = 3,290 Cu. Yds.  
Remaining Location = 41,610 Cu. Yds.  
TOTAL CUT = 44,900 CU.YDS.  
FILL = 39,600 CU.YDS.  
EXCESS MATERIAL = 5,300 Cu. Yds.

\* NOTE: STA. 0+00  
FILL QUANTITY INCLUDES  
5% FOR COMPACTION

Topsoil & Pit Backfill = 5,300 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 0 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



# STEWART PETROLEUM CORPORATION

## CEDAR CAMP #34-15

LOCATED IN GRAND COUNTY, UTAH  
SECTION 34, T15 1/2S, R22E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

**UELS**

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

**LOCATION PHOTOS**

**10 02 07**  
MONTH DAY YEAR


**PHOTO**

TAKEN BY: J.W.

DRAWN BY: C.P.

REVISED: 00-00-00





### LEGEND:

- ⊙ PROPOSED LOCATION**



## STEWART PETROLEUM CORPORATION

**CEDAR CAMP #34-15**

**SECTION 34, T15 1/2S, R22E, S.L.B.&M.**

**1222' FSL 2358' FEL**



**Uintah Engineering & Land Surveying**  
**85 South 200 East Vernal, Utah 84078**  
**(435) 789-1017 \* FAX (435) 789-1813**


# TOPOGRAPHIC MAP

10	02	07
MONTH	DAY	YEAR

<b>SCALE: 1:100,000</b>	<b>DRAWN BY: C.P.</b>	<b>REVISED: 00-00-00</b>
-------------------------	-----------------------	--------------------------







# LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD
- EXISTING 2-TRACK NEEDS UPGRADED



STEWART PETROLEUM CORPORATION

CEDAR CAMP #34-15

SECTION 34, T15 1/2S, R22E, S.L.B.&M.

1222' FSL 2358' FEL



Utah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
MAP

10 02 07  
MONTH DAY YEAR


SCALE: 1" = 2000'

DRAWN BY: C.P.

REVISED: 00-00-00







# LEGEND:

- |                   |                         |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS  | ○ WATER WELLS           |
| ● PRODUCING WELLS | ● ABANDONED WELLS       |
| ● SHUT IN WELLS   | ● TEMPORARILY ABANDONED |



**Utah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**STEWART PETROLEUM CORPORATION**

**CEDAR CAMP #34-15**  
**SECTION 34, T15 1/2S, R22E, S.L.B.&M.**  
**1222' FSL 2358' FEL**


**TOPOGRAPHIC**  
**MAP**

**10 02 07**  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00







**APPROXIMATE TOTAL PIPELINE DISTANCE = 7,647' +/-**

**LEGEND:**

- PROPOSED ACCESS ROAD
- EXISTING 2-TRACK NEEDS UPGRADED
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE

**STEWART PETROLEUM CORPORATION**

**CEDAR CAMP #34-15**

**SECTION 34, T15 1/2S, R22E, S.L.B.&M.**

**1222' FSL 2358' FEL**



**Utah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



**TOPOGRAPHIC**  
**MAP**

**10 02 07**  
MONTH DAY YEAR

SCALE: 1" = 1000'

DRAWN BY: C.P.

REVISED: 00-00-00





# BOP Equipment

5000psi WP

